BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2020-21/OW/WORK_INDENT46073/CALL-4

APPROVED SCHEDULE - B

No.EE/BTP/BBMP/E-PMT/01/2021-22, Date: 30-04-2021

Name of Work:Development of Roads and Drains in ward no 06

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of Kumar N	
				In Figures	In Words
1	26.96	Earthwork excavation for foundation of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in hard soil not exceeding 1.5 m. in depth including dressing the bottom and sides of pits and trenches, stacking the exavated soil clear from edges of excavation with lead upto 50 m. after breaking of clods complete as per specifications and directions of the Engineer incharge.	Cum	484.92	Rupees Four Hundred Eighty Four and Ninety Two Paise Only
2	1.42	Providing and laying in position plain cement concrete of mix 1:4:8(M7.5)with OPC cement @ 180kgs, with 40mm and down size graded granite metal coarse aggregates @0.85cum and fine aggregtes @ 0.57cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation including cost of all materials, labour, HOM of machinery, curing complete as per specifications and directions of the Engineer incharge.	Cum	5510.16	Rupees Five Thousand Five Hundred Ten and Sixteen Paise Only
3	21.6	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for suspended floors, landings, balconies and likes, thickness upto 200 mm including cost of all materials, labour complete as per specificaitons for heights more than 3.50m from ground level. - 0 to 5 mtrs.complete as per specifications and directions of the Engineer incharge.	Sqm	432.0	Rupees Four Hundred Thirty Two Only
4	3.06	Providing and removing centering, shuttering, strutting, propping etc., for edges of slabs and breaks in floors including cost of all materials,labour complete as per specifications and directions of the Engineer incharge.	Sqm	815.4	Rupees Eight Hundred Fifteen and Forty Paise Only
5	2.93	Providing and laying in position reinforced cementconcrete of design mix M25 with OPC cement @ 340kgs, with 20mm and down size graded granite metal coarse aggregates @0.70cum andfine aggregtes @ 0.47cum,with superplastisiser @3lts confirming to IS 9103-1999 Reaffirmed-2008, machine mixed, concrete laid in layers not exceeding 15 cms thick,vibrated fo all works in ground Floor level for roof slabs ,staircase, lintels , beams, retaining walls ,return wall, walls (an thivck	Cum	6593.4	Rupees Six Thousand Five Hundred Ninety Three and Forty Paise Only
6	5.36	Providing and laying cement concrete using 20 mm and down size granite coarse aggregates and fine aggregates of ready mixed concrete (RMC) for R.C.C works laid in 15 cms thick layers and well compacted including vibrating, curing, etc for all super Structure works with all lead and Lift etc., complete (exclusive of cost of steel and fabrication charges) Ready mixed cement for concrete with M-25. complete as per specifications and directions of the Engineer incharge.	Cum	5936.76	Rupees Five Thousand Nine Hundred Thirty Six and Seventy Six Paise Only
7	1.11	Providing T.M.T bars Fe 500 steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications and directions of the Engineer incharge.	tonne	77451.12	Rupees Seventy Seven Thousand Four Hundred Fifty One and Twelve Paise Only

Contractor Signature

Executive Engineer

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of Kumar N	
				In Figures	In Words
8	60.51	Providing and constructing load bearing wall with solid concrete blocks of size 400X200X200mm having block density not less than 1800kg/m3 having a minimum average compressive strength 5.00N/mm2 confirming to IS 2185 (part 1) :2005 and constructed with cement mortar 1:4,as per IS 2572:2005 including cost of materials, labour charges, scaffolding, curing, hire charges of machinaries etc., complete as per specifications and directions of the Engineer incharge.	Sqm	1022.76	Rupees One Thousand Twenty Two and Seventy Six Paise Only
9	60.51	Providing 18mm thick cement plaster in single coat with cement mortar 1:4, to brick masonry including rounding off corners. wherever required smooth rendering, Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications and directions of the Engineer incharge. Head room	Sqm	294.84	Rupees Two Hundred Ninety Four and Eighty Four Paise Only
10	207.276	Providing rough cement plastering 15mm thick in single coat with cement mortar 1:4 to brick masonry for base of dadooing works with sand of approved quality, providing and removing scaffolding, inclding cost of materials, labour, curing complete as per specifications and directions of the Engineer incharge.	Sqm	221.4	Rupees Two Hundred Twenty One and Forty Paise Only
11	451.41	Providing applying two coats of wall putty to inside plastered walls and ceiling using white cement putty . Scrapping and levelling the surface using steel blade and preparing the surface even and smooth by using different grade sand papers, including cost of alll mateerial cost of labour and scaffolding etc. , complete as per specifications and directions of the Engineer incharge.	Sqm	84.24	Rupees Eighty Four and Twenty Four Paise Only
12	170.29	Providing and applying two coats with oil bound washable distemper of approved brand and shade on wall surface including priming coat with distemper primer after throughly brooming the surface free from mortar drops and other foreign matter including preparing the surface even and sand paper smooth, cost of materials, labour, for applying oil bound washable distemper on ceiling and / or sloping roof complete as per specifications and directions of the Engineer incharge.	Sqm	127.44	Rupees One Hundred Twenty Seven and Forty Four Paise Only
13	166.95	Providing and fixing Vetrified glazed tiles of approved make quality & colour of size 900x900x 12mm thick fixed on bed of 12mm thick cement mortar for flooring ,skirting ad jointed with neat cement slurry mixed with pigment to match shade of tiles, including providing spacers at required interval and removing stains etc including Cost of all materials mortar labour etc complete as per specifications and directions of the Engineer incharge.	sqm	1227.96	Rupees One Thousand Two Hundred Twenty Seven and Ninety Six Paise Only
14	3.33	Providing Ceramic tiles of size 30x30cms 6mm thick of approved make ,shade and size for flooring, treads of steps and landings laid on a bed of 12mm thick, cement mortar 1:3 mix, flush pointing with white cement using colour pigment , including cost of materials, labour, curing, complete as per specifications and directions of the Engineer incharge.	sqm	1306.8	Rupees One Thousand Three Hundred Six and Eighty Paise Only
15	218.5	Providing skirting, dado, rises of steps with colour glazed tiles 30X60 cms 6mm thick with border of size 30 x 10 cms on 10mm thick cement plaster 1:3 and jointed with white cement slurry over rough plaster surface (excluding cost of rough plastered surface which should be measured and paid separately) using glazed tiles of approved make and size including cost of materials, labour, complete as per specifications and directions of the Engineer incharge.	Sqm	1762.56	Rupees One Thousand Seven Hundred Sixty Two and Fifty Six Paise Only

Contractor Signature

Executive Engineer

Sl No.	Approved Qty.	Description	Unit	Approved Tender Rates of Kumar N	
				In Figures	In Words
16	40.47	Waterproofing of RCC Terrace / podium slab / toilet / utilities / water retaining structure by preparing the surface by chipping and cleaning and Grouting of Honey comb, voids,cracks / construction joints with cement slurry (1kg cement added in 10 ltr of water) added with 100gm of inorganic accelerator, followed by spraying of liquid biological modified alkaline earth silicates @ 0.40 ltr per sqm on whole surface to reduce the micro porosity and allowing it to dry, curing the surface for the silicates to penetrate deeper into the concrete and spraying waterproofing impregnate liquid containing silane and silanol linear copolymer @ 0.50 ltr per sqm and finally applying polymer slurry made out of cross linked acrylic / styrene / butadiene & cement in the ratio of 1:0.1, @0.50kg/sqm on the whole surface, including all labour charges tools and equipments, all complete as per specifications and directions of the Engineer incharge.	Sqm	568.08	Rupees Five Hundred Sixty Eight and Eight Paise Only
17	22.8	Providing and fixing 65mmx90mm GRP Doorframe fabricated using E-Glass Chopped Strand Mat (CSM). U.V-stabilized Isopthalic Gelcoat and Isopthalic resin. The thickness of the GRP skin shall not be less than 2.0 mm. The doorframe consists of four segmens, which are provided with plug-in-socket arrangement in-situ in the mould. The segments are plugged in and are joined together by means of screws. The GRP frame shall be provided with wooden reinforcement of 6 locations fro high screw holding capacity for fixing metallic hold fast and shall be consolidated by filling with medium density foam/Plaster with fibre reinforcement. Six Numbers of 260mmx25mmx5mm size S shaped M.S. flat hold fast shall be provided with the frame. complete as per specifications and directions of the Engineer incharge.	m	486.0	Rupees Four Hundred Eighty Six Only
18	2.7	Providing and fixing in position fully panelled Honne wood shutters for doors, styles and rails of 40mm. thick with bottom and lock rails 180mm wide top rail and styles 100mm wide as per drawing and panels of 25mm thick including cost of materials, labour, HOM of machineries complete as per specifications and directions of the Engineer incharge.	Sqm	5099.76	Rupees Five Thousand Ninety Nine and Seventy Six Paise Only
19	0.9	Providing and fixing in position fully panelled Honne wood shutters for doors, styles and rails of 40mm. thick with bottom and lock rails 180mm wide top rail and styles 100mm wide as per drawing and panels of 25mm thick including cost of materials, labour, HOM of machineries complete as per specifications and directions of the Engineer incharge. Head Room	Sqm	5104.1	Rupees Five Thousand One Hundred Four and Ten Paise Only
20	6.3	Providing and fixing factory made single leaf rigid GRP Sandwich composite door shutter of 40 mm thick, laminated with two GRP skins with wood grain finish, fabricated using U.V-stabilized Isopthalic Gelcoat and one layer of 450 gns E-Glass Chopped Strand Mat (CSM), impregnated with orthopthalic polyester resin. The thickness of the skins shall not be less than 1.5mm. Expanded Polystyrene (EPS) structural foam panel of 37mm thickness and a density of 20 Kg/m3 shall be used as core material. Wooden reinforcements made of Seasoned Salwood block of cross section not lessthan 36mmx32mmand also necessary salwood reinforcements for fixing the metal fittings such as tower bolts, aldrops, handles, etc. shall be provided. A structural adhesive compatible with EPS foam shall be used for bonding the core material, the salwood reinforement and the skins. The material and process for manufacturing the door shutters shall confirm to RV-TIFAC Composites Design Centre Standards and specifications and the door shutters tested in confiramation to IS 4020-1994. The finish of shutter will be plain coulur White/IVORY/Beige/Light Grey or any other colour using high quality pigments. Excluding cost of fixtures and inclusive of supply of shutters to respective work spot. complete as per specifications and directions of the Engineer incharge	Sqm	4104.0	Rupees Four Thousand One Hundred Four Only

Contractor Signature

Executive Engineer

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of Kumar N	
				In Figures	In Words
21	5.3	Providing and applying painting two coats (excluding priming coat) on new wood surface and / or wood based surface with enamel paint to give an even shade, cleaning the surface of all dirt, dust and foreign matter, sand papering including cost ofmaterials, labour, complete as per specifications and directions of the Engineer incharge	Sqm	104.76	Rupees One Hundred Four and Seventy Six Paise Only
22	17.55	Providing and fixing in position aluminium windows and ventilators as per approved drawings with sliding shutters using three track window frame of size 92x31.75mm bottom section 1.3mm thick, weight 1.07kg/m; sides and top sections 1.3 mm, thick, weight 0.933 kg/m.shutter frame section comprising top and bottom section of size 40mmx18mm, wall thickness 1.25mm. weight 0.417 kg./m. shutter side outer 40mmx18mm. wall thickness 1.25mm. weight 0.417 kg/m, shutter interlock section 40mmx26.7mm wall thickness 1.1 mm. thick, weight 0.469 kg/m, the shutters mounted on nylon rollers with approved quality of fixtures such as aluminium handles tower bolts etc.; providing and fixing 5.5mm. thick plain glass for shutters fitted with rubber beading all aluminium sections including cutting to required length, joints mitred subdividing the frame tenonned and rivetted, in the assembled frame, stiffened with end clips for corners, angles etc., and fixed to the walls, lintels, floor beams/cills as the case may be, with necessary steel screws, raul plugs or teak wood gatties including cutting masonry or concrete and making good the original surface using cement mortar - using aluminium section powdered coated to a minimum of 60- 70 microns with exterior durable pure polyester grade powder of approved qualitycomplete as per specifications and directions of the Engineer incharge	Sqm	4789.8	Rupees Four Thousand Seven Hundred Eighty Nine and Eighty Paise Only
23	16.74	Providing and fixing Stainless steel staircase raling as per Chief Architect Drawing No. 11520/ HRSC with hand rail 50mm dia 16 guage hollow pipe welded to vertical hollow 50mm dia pipe of 16 guage, stainless steel vertical pipe spaced at 1.20m regular intervals, and 5 Nos of 25mm dia. Stainless steel hollow horizontal pipe are welded to vertical 50mm dia hollow pipe. The entire assembly is fixed to staircase concrete by using expansion bolts by drilling concrete etc., complete including cost of materials, labour, HOM of machineries and electrical charges, etc., complete as per specifications. Pg 45 Item no.7.38	Sqm	6502.68	Rupees Six Thousand Five Hundred Two and Sixty Eight Paise Only
24	105.99	Providing and finishing external walls in two coats with waterproof cement paint of approved brand and shade to give an even shade after throughly brooming the surface to remove all dirt and loose powdered material, free from mortar drops and other foreign matter cost of materials, labour, complete as per specifications and directions of the Engineer incharge	Sqm	96.12	Rupees Ninety Six and Twelve Paise Only
25	60.51	Providing and finishing external walls in two coats with waterproof cement paint of approved brand and shade to give an even shade after throughly brooming the surface to remove all dirt and loose powdered material, free from mortar drops and other foreign matter cost of materials, labour, complete as per specifications and directions of the Engineer incharge Head Room	Sqm	100.44	Rupees One Hundred and Forty Four Paise Only
26	0.37	Providing Honne wood frames of doors, windows, clerestory windows,ventilators and other frames , wrought, framed or assembled including making plaster groves (excluding cost of cement concrete and side clamps),but including cost of materials, labour, HOM of machineries complete as per specifications and directions of the Engineer incharge	Cum	94612.3	Rupees Ninety Four Thousand Six Hundred Twelve and Thirty Paise Only
27	3.78	Providing and fixing in position fully panelled Honne wood shutters for doors, styles and rails of 40mm. thick with bottom and lock rails 180mm wide top rail and styles 100mm wide as per drawing and panels of 25mm thick including cost of materials, labour, HOM of machineries complete as per specifications and directions of the Engineer incharge	Sqm	5099.76	Rupees Five Thousand Ninety Nine and Seventy Six Paise Only

Contractor Signature

Executive Engineer

S' No.	Approved Qty.	Description	Unit	Approved Tender Rates of Kumar N	
				In Figures	In Words
28	330.75	Providing and fixing M.S.grill work for windows and ventilators weighing 21kg/sqm using M.S. flats, or M.S. square rods, or combination of M.S. flats and square rods as per approve design, drawing including cutting steel sections and welding the same to required pattern with a coat of red lead primer, cost of materials, fixtures, labour and HOM of machinery complete as per specifications and directions of the Engineer incharge	kgs	7.6	Rupees Seven and Sixty Paise Only
29	15.75	Providing and applying enamel metal paint two coats (excluding priming coat) over new steel or other metal surface brushing to give an even shade after cleaning oil, grease, dirt and other foreign matter, including cost of materials, labour, complete as per specifications and directions of the Engineer incharge	Sqm	102.6	Rupees One Hundred Two and Sixty Paise Only
30	54.84	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for foundations, footings, bases of columns for mass concrete including cost of all materials, labour complete as per specifications and directions of the Engineer incharge	Cum	278.64	Rupees Two Hundred Seventy Eight and Sixty Four Paise Only
31	8.2	Providing and laying in position reinforced cement concrete of Design mix M25 with OPC cement @ 340kgs, with 20mm and down size graded granite metal coarse aggregates @0.70 cum and fine aggregtes @ 0.47cum, with super plasticisers @ 3 liters confirming to is 9103-1999 reafirmed-2008 at machine mixed, concrete laid in layers not exceeding 15 cms thick, vibrated for all works in foundation for footings, pedastals, retaining walls, return walls, walls (any thickness) including attached pilasters, columnspillars, posts, struts, buttresses, bed blocks, anchor blocks & plinths etc., including cost of all materials, labour, HOM of machinery, curing, complete but excluding cost of reinforcement complete as per specifications and directions of the Engineer incharge	Cum	6276.96	Rupees Six Thousand Two Hundred Seventy Six and Ninety Six Paise Only
32	1.02	Providing T.M.T bars Fe 500 steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications and directions of the Engineer incharge	Tonne	76643.28	Rupees Seventy Six Thousand Six Hundred Forty Three and Twenty Eight Paise Only
33	4	Providing 20mm square M.S footrest and fixing in manhole Nos 232.00 with M 10 cement concrete block of 20x20x10cms, using 20mm and down size metal of size including cost of materials, labour charges, curing complete as per specifications and directions of the Engineer incharge	No.s	298.08	Rupees Two Hundred Ninety Eight and Eight Paise Only
34	26.96	Conveying the excavated earth, debries etc., with all lead and lifts including loading and unloading charges etc., complete as per specifications and directions of the Engineer incharge	Cum	67.09	Rupees Sixty Seven and Nine Paise Only
35	30	Providing and fixing to wall, ceiling and floor unplasticised PVC 6.00 kgs/sqcm working pressure with pipe fittings, wall clips etc., and making good the wall, ceiling and floor for sanitary pipelines including cost of all materials,labour charges, HOM of acquirements and testing complete as per specifications.For Rain water pipe.complete as per specifications and directions of the Engineer incharge -do - 110 mm dia	m	468.72	Rupees Four Hundred Sixty Eight and Seventy Two Paise Only
36	23	Providing and fixing to wall, ceiling and floor unplasticised PVC 6.00 kgs/sqcm working pressure with pipe fittings, wall clips etc., and making good the wall, ceiling and floor for sanitary pipelines including cost of all materials,labour charges, HOM of acquirements and testing complete as per specifications.For Rain water pipe.complete as per specifications and directions of the Engineer incharge -do - 160 mm dia	m	921.24	Rupees Nine Hundred Twenty One and Twenty Four Paise Only

Contractor Signature

Executive Engineer

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of Kumar N	
				In Figures	In Words
37	4	Constructing brick masonry inspection chamber 600x600mm, and 450mm depth, (clear inside dimension) for single pipeline, using table moulded non-modular bricks of class designation 50 in cement mortar 1:5, C.I cover withframe (light duty) 455x610mm internal dimensions, total weight of cover with frame to be not less than 38 kg (weight of cover 23kg and weight of frame 15 kg) R.C.C. top slab with cement concrete M 15 with 20mm and downsize granite metal, foundation concrete M 5 with 40mm and downsize granite metal inside plastering 12mm thick with cement mortar 1:3, finish smooth with a floating coat of cement on walls and bed concrete complete as per standard design including cost of materials, labour charges, curing complete as per specifications. Specification No. KBS 600x600mm and 450mm depth (clear inside dimension) for single pipeline, using table moulded non-modular bricks of class designation 50 in cement mortar 1:5, C.I cover withframe (light duty) 600x600mm. complete as per specifications and directions of the Engineer incharge	Nos.	9169.2	Rupees Nine Thousand One Hundred Sixty Nine and Twenty Paise Only
38	2	Providing and placing on terrace, polyethylene water storage tanks with manhole lid and suitable locking arrangements, making holes of suitable diameter for inlet, outlet and over flow pipes, including cost of all materials, labour, transport charges, HOM of equipments and testing complete as per specifications and directions of the Engineer incharge	Each	7374.24	Rupees Seven Thousand Three Hundred Seventy Four and Twenty Four Paise Only
39	12	Providing and fixing in position brass bib cock of approved quality 20mm nominal bore including cost of all materials, labour and HOM of equipments with all leads complete as per specifications and directions of the Engineer incharge	Each	186.84	Rupees One Hundred Eighty Six and Eighty Four Paise Only
40	5	Providing and fixing in position brass stop cock of approved quality 20mm nominal bore including cost of all materials, labour and HOM of equipments with all leads complete as per specifications and directions of the Engineer incharge	Each	152.28	Rupees One Hundred Fifty Two and Twenty Eight Paise Only
41	2	Providing and fixing in position brass gate valve with C.I wheel of approved quality (screwed end) 20mm nominal bore including cost of all materials, labour and HOM of equipments with all leads complete as per specifications and directions of the Engineer incharge	Each	362.88	Rupees Three Hundred Sixty Two and Eighty Eight Paise Only
42	5	Providing and fixing unplasticised PVC connection pipe with brass union 15mm nominal bore 450 mm length of PVC connection including cost of all materials, labour and HOM of equipments with all leads complete as per specifications and directions of the Engineer incharge	Set	285.12	Rupees Two Hundred Eighty Five and Twelve Paise Only
43	3	Providing and fixing in position 40mm nominal bore non return valve vertical type of approved make including cost of all materials, labour and HOM of equipments with all leads complete as per specifications and directions of the Engineer incharge do- 25mm dia	Nos	513.0	Rupees Five Hundred Thirteen Only
44	3	Providing and fixing in position 40mm nominal bore non return valve vertical type of approved make including cost of all materials, labour and HOM of equipments with all leads complete as per specifications and directions of the Engineer incharge do- 32mm dia	Nos	806.76	Rupees Eight Hundred Six and Seventy Six Paise Only
45	20	Providing and fixing Chorinated Poly Venyl Chloride (CPVC) pipes conforming to IS 15778, having thermal stability for hot and cold water supply including all CPVC plain and brass threaded fittings including fixing the pipe with clamp at 1.00 mtr spacing. This includes jointing of pipes and fittings with one step CPVC solvent cement & the cost of cutting chases & making good the same including testing of joints complete as per specifications and directions of the Engineer incharge 20mm nominal OD pipes	m	253.8	Rupees Two Hundred Fifty Three and Eighty Paise Only

Contractor Signature

Executive Engineer

S No.	Approved Qty.	Description	Unit	Approved Tender Rates of Kumar N	
				In Figures	In Words
46	22	Providing and fixing Chorinated Poly Venyl Chloride (CPVC) pipes conforming to IS 15778, having thermal stability for hot and cold water supply including all CPVC plain and brass threaded fittings including fixing the pipe with clamp at 1.00 mtr spacing. This includes jointing of pipes and fittings with one step CPVC solvent cement & the cost of cutting chases & making good the same including testing of joints complete as per specifications and directions of the Engineer incharge 25mm nominal OD pipes	m	316.44	Rupees Three Hundred Sixteen and Forty Four Paise Only
47	20	Point wiring using copper wire without switch (Class A material). Supplying and wiring adopting loop system in existing PVC conduit/casing capping using 2X1.5Sqmm(phase &Netural) &1X1.0 Sqmm (Earth Wire) FRLSmultistrand PVC insulated ,2x1.5sqmm copper confirming to the GTP With a 6Amps flusg type SP control switch shall be fixed on the existing plastic sheet / gand box .the other end of the wire shall be terminated with sufficient loose length in a wood/PVC round block, complete for each outlet. Short point upto 3m complete as per specifications and directions of the Engineer incharge	Point	200.0	Rupees Two Hundred Only
48	15	Point wiring using copper wire without switch (Class A material). Supplying and wiring adopting loop system in existing PVC conduit/casing capping using 2X1.5Sqmm(phase &Netural) &1X1.0 Sqmm (Earth Wire) FRLSmultistrand PVC insulated ,2x1.5sqmm copper confirming to the GTP With a 6Amps flusg type SP control switch shall be fixed on the existing plastic sheet / gand box .the other end of the wire shall be terminated with sufficient loose length in a wood/PVC round block, complete for each outlet. Medium point above 3m - 6m complete as per specifications and directions of the Engineer incharge	Point	275.0	Rupees Two Hundred Seventy Five Only
49	120	Concealed Conduit System - Supplying heavy gague PVC conduit pipe 20/25/32 mm dia 2mm thick confirming to IS 2509 with suitable size bends metal/pvc junction boxes, abhesive paste ets, and running befour concreting and slab. The conduit should de tied to the reinforcement rods by using binding wires and unused ways of junction boxes and pipe ends should be covered using PVC end enclosures, run with 18SWG GI fisg wire whereever necessary 19/20mm dia, 2mm thick complete as per specifications and directions of the Engineer incharge	Rm	40.0	Rupees Forty Only
50	175	Concealed Conduit System - Supplying heavy gague PVC conduit pipe 20/25/32 mm dia 2mm thick confirming to IS 2509 with suitable size bends metal/pvc junction boxes, abhesive paste ets, and running befour concreting and slab. The conduit should de tied to the reinforcement rods by using binding wires and unused ways of junction boxes and pipe ends should be covered using PVC end enclosures, run with 18SWG GI fisg wire whereever necessary 25mm dia, 2mm thick complete as per specifications and directions of the Engineer incharge	Rm	53.0	Rupees Fifty Three Only
51	50	Groove cutting : Supplying heavy gauge conduit PVC 25/2mm of s thick heavy with suitable size bend , metal junction boxes, adhesive pastes etc, by groove cutting in a wall and fixing by bracing U or J hooks and cement plastering up to the surface and run with 18SWG GI fish wire run throughout the conduit where ever necessary. 19/20mm dia, 2mm thick complete as per specifications and directions of the Engineer incharge	Mtr	51.0	Rupees Fifty One Only
52	65	Groove cutting : Supplying heavy gauge conduit PVC 25/2mm of s thick heavy with suitable size bend , metal junction boxes, adhesive pastes etc, by groove cutting in a wall and fixing by bracing U or J hooks and cement plastering up to the surface and run with 18SWG GI fish wire run throughout the conduit where ever necessary. 25mm dia, 2mm thick complete as per specifications and directions of the Engineer incharge	Mtr	54.0	Rupees Fifty Four Only

Contractor Signature

Executive Engineer

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of Kumar N	
				In Figures	In Words
53	18	Supplying and flush modular poweder coated / galvanized metal box suitable for mounting modular switch plates. the box should be firmil flush mounted after due groove cutting in brick /stone/C.C wall 1 - 3 Way complete as per specifications and directions of the Engineer incharge	Each	95.0	Rupees Ninety Five Only
54	15	Supplying and flush modular poweder coated / galvanized metal box suitable for mounting modular switch plates. the box should be firmil flush mounted after due groove cutting in brick /stone/C.C wall 4 - 5 Way complete as per specifications and directions of the Engineer incharge	Each	105.0	Rupees One Hundred Five Only
55	120	Wiring for lighting/power circuit using Grade using one of FRLS PVC insulated 1100 volts grade, multistrand copper with low conductor resistance single core wire in open or concealed system of wiring. With specified IS-694: confirming to Latest amendements. 1.5sqmm complete as per specifications and directions of the Engineer incharge	Rm	20.05	Rupees Twenty and Five Paise Only
56	195	Wiring for lighting/power circuit using Grade using one of FRLS PVC insulated 1100 volts grade, multistrand copper with low conductor resistance single core wire in open or concealed system of wiring. With specified IS-694: confirming to Latest amendements. 2.5sqmm complete as per specifications and directions of the Engineer incharge	Rm	32.0	Rupees Thirty Two Only
57	50	Wiring for lighting/power circuit using Grade using one of FRLS PVC insulated 1100 volts grade, multistrand copper with low conductor resistance single core wire in open or concealed system of wiring. With specified IS-694: confirming to Latest amendements. 4sqmm complete as per specifications and directions of the Engineer incharge	Rm	45.0	Rupees Forty Five Only
58	8	Supplying and fixing Metal Fan Box with Round Hook complete as per specifications and directions of the Engineer incharge	Nos	85.0	Rupees Eighty Five Only

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92